



The **110D-3600-C900 frame** can be used for single-sided or double-sided applications.

Pre-Term 110D Floor Frames with Module

Homaco® has your pre-term solution for all 110D frames and modules. Modules feature 18-foot cascading, connectorized stubs and can be mounted on Homaco standard 110D frames or directly on the wall. Frames are equipped with one pre-term module (110D-900-C900) shipped in a separate box.

For floor frame applications, simply order a frame, then order the number of 110D-900-C900 modules needed to meet your requirements. Frames accommodate up to four 900-pair modules on each side to terminate 3,600 pairs per side.

Features:

- 100% factory tested
- Reduces installation time
- Reduces termination costs per pair
- Each module terminates 900 pairs
- Cascades help minimize congestion
- Easy to order in the exact capacity needed

Specifications:

- Velcro® cable retainers manage vertical cables in channel uprights
- 110D blocks terminated using 5-pair 110 clips
- 18-foot cascading stubs terminated with 25-pair telco female connectors
- Modules terminated in common horizontal wiring pattern
- Riser (CMR) rated 100-pair, 24-gauge, unshielded twisted pair cable
- Frame mounts up to four 900-pair modules on each side
- Modules supplied with wall-mount bracket and all required hardware

Catalog No.	Dimensions*	Ship Weight
110D-3600-C900	84.00"H x 37.50"W x 16.13"D	240 lbs

*Dimensions do not include cascading cable stubs. Stub length is 18 feet from exit point on module.



Pre-Term 110D Module (110D-900-C900)

Pre-Term 110D Module

Module features 18-foot cascading, connectorized stubs and mount to Homaco 110D frames or directly to the wall. For floor frame applications, simply order a 110D-3600-C900 frame, then order the number of modules needed to meet requirements.

Features:

- Each module terminates 900 pairs
- 110D blocks terminated using 5-pair 110 clips
- 18-foot cascading stubs terminated with 25-pair telco connectors
- Module terminated in common horizontal wiring pattern
- Module supplied with wall-mount bracket and all required hardware
- Cascades help minimize congestion
- Riser (CMR) rated 100-pair, 24-gauge, unshielded twisted pair cable

Catalog No.	Dimensions*	Type	Ship Weight
110D-900-C900	13.75"H x 37.25"W x 7.75"D	Female	105 lbs
110D-900-C900/MCN	13.75"H x 37.25"W x 7.75"D	Male	105 lbs

*Dimensions do not include cascading cable stubs. Stub length is 18 feet from exit point on module.